

Board of Supervisors

Susan B. Stimpson, Chairman
Cord A. Sterling, Vice Chairman
Jack R. Cavalier
Paul V. Milde, III
Ty A. Schieber
Gary F. Snellings
Robert "Bob" Thomas, Jr.

Anthony J. Romanello, ICMA-CM
County Administrator

March 21, 2012

BID #327122

ADDENDUM #2

All prospective Bidders are hereby advised to make the following changes and/or additions to the Bid Documents in their possession as issued for Bid #327122 for the Renovation of the Science Classrooms, Stage Area, and Bathrooms at North Stafford High School for the Stafford County School Board:

General

1. This Addendum is hereby made a part of the Contract Documents issued to modify, alter, revise, or explain the original drawings and/or specifications. The contents of this Addendum will take precedence over the original instruments and shall be bound with the specifications.
2. All Bidders shall acknowledge the receipt of this Addendum in the space provided on the **Bid Price Schedule (Page 41)**.

GENERAL:

All Planholders are requested to attach this Addendum to the inside front cover of each Project Manual. Please inform all concerned that the Documents are modified by this Addendum.

The following revisions, additions, and clarifications are hereby made a part of the Contract Documents and supersede or otherwise modify the provisions of the published *Project Manual* and *Drawings*, dated February 13, 2012, and Addendum No. 1, dated March 12, 2012.



1. REVISIONS TO THE PROJECT MANUAL

SECTION 116143 - STAGE CURTAINS

REFER to pages 116143-4 and 116143-5, PART 3-EXECUTION.

DELETE D. MAINTENANCE entirely."

2. REVISIONS TO THE DRAWINGS

DRAWING A2.1.3

REFER to Toilet Keynotes.

ADD the following clarification to Toilet Keynote 2:

In each of the eight wheelchair accessible toilet stalls, provide one 36" minimum long horizontal rear wall grab bar, one 42" minimum long horizontal side wall grab bar, and one 18" long vertical side wall grab bar. In lieu of the rear and side horizontal grab bars, a continuous L-shaped grab bar, 42" minimum long in the rear and 54" minimum long at the side, are acceptable in each of the eight wheelchair accessible toilet stalls.

In each of six ambulatory accessible toilet stalls, provide two 42" minimum long horizontal side wall grab bars and two 18" long vertical side wall grab bars.

Install all grab bars mentioned above at heights and locations within each wheelchair accessible toilet stall and each ambulatory toilet stall per sections 604.5.1 and 604.5.2 of ICC/ANSI A117.1-2003.

DRAWING A3.1

REFER to Stage Curtain Notes.

ADD the following note:

5- Remove the two existing pieces of curtain pipe at the location of the new middle border and provide a continuous 58'-0" long batten (pipe) in the same location with supports at the same height as the two existing remaining battens.

REFER to Stage Curtain Chart, BORDER line, TRACK column.

DELETE the word “EXISTING”.

ADD the following:

Front and rear border battens are existing, the middle border batten is new.

REFER to Finish Schedule.

ADD the following to the NOTES column of Biology Classrooms 301, 303, 319, 321, 322, 323, 324 and 325, Physics Classroom 302, Chemistry Classrooms 318 and 320, and Marine Biology Tank Room 325A:

Paint existing steel door frames. Do not paint existing natural finish doors.

DELETE the following note from the CEILING column of Stage S1:

“EXP-PT*”.

ADD the following note to the CEILING column of Stage S1:

Underside of existing roof deck is 32’-8”+/- above finish floor. Do not paint exposed roof structure and underside of existing roof deck above existing ACP ceiling to remain.

DELETE the following note from the CEILING column of South Stage Wing S2 and North Stage Wing S5:

“EXP-PT”.

ADD the following note to the CEILING column of South Stage Wing S2 and North Stage Wing S5:

Underside of existing roof deck is 32’-8”+/- above finish floor. Paint exposed roof structure and underside of existing roof deck.

END OF ADDENDUM NO. 2