

## Board of Supervisors

Jack R. Cavalier, Chairman  
Gary F. Snellings, Vice Chairman  
Meg Bohmke  
Paul V. Milde, III  
Laura A. Sellers  
Cord A. Sterling  
Robert "Bob" Thomas, Jr.

Anthony J. Romanello, ICMA-CM  
County Administrator

May 8, 2014

**Bid #513142**

### **ADDENDUM #3**

The following information is provided for Bid #513142 for the Construction of Claiborne Run Pump Station Generator. All prospective Bidders are hereby advised to make the changes to the Bid Documents in their possession as follows:

#### General:

1. This Addendum is hereby made a part of the Contract Documents issued to modify, alter, revise or explain the original drawings and/or specifications. The content of this Addendum will take precedence over the original instruments and shall be bound with the specifications.
2. All Bidders shall acknowledge the receipt of this Addendum in the space provided on Page 00300-2 of the Bid Form.

The purpose of Addendum #3 is to extend the bid date and provide the following clarifications:

**NEW OPENING BID DATE: THE OPENING DATE HAS BEEN EXTENDED TO THURSDAY, MAY 15, 2014 AT 2:00 P.M.** The location will remain the same.

The following plan sheets shall be changed as follows:

**Sheet S2.1: Sheet S2.1 is in conflict with the Sheet E3.0 for the routing of the electrical conduit. The conduit shall be routed below the concrete slab and penetrate the retaining wall as indicated on Sheet E3.0. Delete Plan Keynote 9 on Sheet S2.1.**

**Sheet C4.0: The sidewalk behind the curb and gutter shown to be removed on this sheet must also be removed in order to accommodate the new concrete apron as shown on Sheet C5.0.**

**Sheet S2.1: The generator and fuel tank pad shall be extended 5.8 feet to the southwest to tie into the concrete apron as shown on Sheet C5.0. The typical slab section and turned down slab details shall apply with the exception that a concrete base for the fence posts penetrating the slab shall be required per Sheet C2.2. Provide a paper joint between the edge of the turned down slab and concrete apron.**

END OF SECTION

